


# Manchac Landbridge Diversion

## Sediment Diversion


Project ID: 001.DI.100



### Description

A structure in the existing western spillway guide levee to divert 2,000 cfs thereby increasing freshwater exchange with adjacent wetlands.

### Scale of Influence



### Project Location

St. Charles Parish; St. John Parish

### Project Duration

Planning, Engineering, and Design is estimated to take 4 years.  
Construction is estimated to take 2 years.

### Project Cost Estimate

	Estimated Cost
Planning/Engineering & Design	\$9,400,000
Construction	\$118,000,000
Operations & Maintenance	\$20,800,000
<b>Total</b>	<b>\$148,200,000</b>

### Land Area Built or Maintained\*

Near Term (Year 20)	-149 acres
Long Term (Year 50)	9,992 acres

\*Based on the high environmental scenario.

### Other Nearby Projects in the Master Plan

